



Cleveland County
NORTH CAROLINA

No Authorization to Construct

IMPROVEMENT PERMIT

Improvement Permit Number: 177326

Parcel ID: 25170

AIP Property Group LLC		2520 Wildwood dr		603-361-7909
Owner/Legal Representative		Property Address		Phone Number
2127	Wildwood	n/a	n/a	0.56 acres
State Rd #	S/D-MHP	Section/Phase	Lot Number	Lot Size/Acreage

Watershed Yes Water Classification WSIII-CA Critical Area Yes

Directions to property: From S Post Rd turn RT onto Elizabeth Ave continue onto Oak Grove rd turn LT onto China Ave turn RT Wildwood dr dest RT

Permit Type: <u>New Installation</u>	No. of bedrooms: <u>3</u>	No. of <u>residents</u> /employees: <u>6 max</u>
Wastewater Type: <u>Single Family</u>	Design flow (GPD): <u>360</u>	LTAR <u>0.3</u>
Construction Type: <u>House</u>	System Type: <u>25% reduction</u>	Insp. Freq. <u>5 yrs</u>
Foundation Type: <u>Slab</u>	Tank Size: Septic <u>1000g</u>	Pump <u>1000g</u> Grease Trap <u>N/A</u>
Water Supply: <u>Public/Municipal</u>	Sq. Ft. <u>900'</u> # of lines <u>4</u>	Width <u>36"</u> Length <u>300'</u> tot On Ctr <u>9'</u>
Well Permit No: <u>n/a</u>	Trench Depth (high side) <u>24"</u>	Aggregate <u>n/a</u> Cover <u>10"-12"</u>
	Repair Wastewater System Type: <u>pump to drip</u>	100% <u>Yes</u>

Condition(s) of Issuance: Maintain 5' from foundation. 10' from P/L. 10' from H20 supply line. Install according to all NC rules and regulations. Construction authorization will not be released until survey is recorded.

An authorized agent of DHHS shall have issued this Improvement Permit after determining that the site is suitable or provisionally suitable and that a system can be installed so as to meet the provisions of the Rules, and items required in G.S. 30A-336(a). An Improvement Permit for which a plat is provided shall be valid without expiration and an Improvement Permit for which a site plan is provided shall be valid for 60 months from the date of issue provided in G.S. 130A-335(f) and G.S. 130A-336(a). The Improvement Permit is transferable to subsequent owners except as provided in G.S. 130A-335(f) and G.S. 130A-336(a).


The Construction Authorization shall be issued by an authorized agent for installation of a wastewater system when it is found that the Improvement Permit conditions and rules of this Section 15A NCAC 18A .1937 are met.

If the installation has not been completed during the period of validity of Construction Authorization, the information submitted in the application for an Improvement Permit or Construction Authorization is found to be incorrect, falsified or changed, or the site is altered, the Improvement Permit and/or Construction Authorization shall become invalid, and may be suspended or revoked.

This Permit Is Valid For: 5 Years

Attached: Site Sketch

Owner/ Legal Representative _____ Date _____
CCEH # 6 REV. 01/20



Gabrielle Carter, REHSI Date 10/17/2023